



**115 W. Lincoln Avenue - Salem United Methodist Church – Noncontributing
(ARC Case 03-25)**

Located at the corner of South Hough and West Lincoln Avenue is the Salem United Methodist Church which is a two-story, stone veneer, Neogothic church originally built in 1893 and rebuilt in 1951. The building has an exterior of random course stone, a hip and gable roof of asphalt shingles and a concrete foundation. On the main (N) façade which faces Lincoln Avenue is a one-story entry vestibule with an arched entrance containing original double wood doors. Over the doors is an arched, leaded and stained glass transom. Recessed behind the entrance bay is a two-story, rectangular bell tower with arched louvered vents and stone pilasters. The main section of the church on the primary façade has stone and concrete wall buttresses. In the gable field is a quatrefoil attic window. Windows are one-over-one wood sash of diamond light stained glass design on the main façade. Some windows on the east façade are arched.

At the rear is a two-story education wing with added anodized aluminum windows.



121 W. Lincoln Avenue - Contributing

This is a two-story rectangular American Foursquare dwelling built ca. 1900. The dwelling has a stone foundation, a hipped roof of asphalt shingles, an interior brick chimney and an exterior of vinyl siding. On the main (N) façade is a one-story, full-width porch with ca. 1925, square tapered, Doric motif, wood columns and a railing with square wood balusters. The main entrance retains its original, single-light and three wood panel door and single-light glass and wood sidelights. Windows are original one-over-one double hung, rectangular wood sash. On the second story central bay is a diamond light fixed window flanked by large brackets. On the east façade is a two-story polygonal bay with three, one-over-one wood sash windows. At the roofline on the main and west facades are hipped roof dormers with paired diamond light attic windows.



Attached to the dwelling on the west façade is a ca. 1990, hipped roof garage with a nine-light and metal panel pedestrian door and a sixteen-metal panel overhead track door. - **Noncontributing**



127-129 W. Lincoln Avenue - Contributing

Located at 127-129 W. Lincoln is a two-story asymmetrical Italianate style dwelling built ca. 1875. The dwelling has a brick foundation, a hipped roof of asphalt shingles, an interior brick chimney and an exterior of aluminum siding. The primary entrance faces the east façade and not the Avenue façade. On the east façade is a single-story entry porch with a hipped roof supported by original milled columns, milled brackets, wood dentils and a railing and frieze of milled cut-out panels. The main entrance retains its original, five-panel wood door with a projecting bracketed cornice with wood dentils. Also on the east façade is a single-story bay window with three, one-over-one wood sash windows, a bracketed cornice and wood dentils. At the northeast corner of the building is a two-story, rectangular, gable roof bay with large fixed one-light windows with three, stained glass sections. Each window is outlined with wood pilaster strips and bulls eye corner blocks. Below the first floor window are arched wood panels with pellet molding and below the second-story bay window are inset wood panels. On the north façade is a picture window with a single-light window fixed with three, stained glass sections. Windows overall are one-over-one double hung wood sash with bracketed cornices and wood dentils. At the roofline are paired eave brackets and gable returns. In the gable fields are circular attic vents with frame keystones and shoulders. On the west façade is an entrance with an original entry porch reconstructed ca. 1950 with square posts.





132 W. Lincoln Avenue - Noncontributing

Located at 132 West Lincoln Avenue is a ca. 1950, frame, single-story duplex. This property was altered ca. 1980 with added board and batten siding.

At the rear of the duplex is a two-bay, gable roof garage with shiplap siding and added paneled metal garage doors. - **Noncontributing**



133 W. Lincoln Avenue – Contributing (ARC Case 01-08)

This is a two-story, gable front Folk dwelling built in 1910. The house has a brick foundation, an interior brick chimney, a front gable roof of asphalt shingles and an exterior of weatherboard and masonite siding. On the main (N) façade is a single-story, full-width porch rebuilt in 2001 with square wood columns and a square wood baluster railing. The main entrance retains its original, single-light glass and wood door and single-light original storm door. Windows are original, one-over-one double hung rectangular wood sash. The center section of the picture window on the first floor's main façade has a diamond-light patterned transom. In the gable field on the main façade are paired, one-over-one double hung wood sash windows.

Located off the southeast façade is a ca. 1990, frame garage with a gable roof of asphalt shingles, an exterior of weatherboard and a thirty-two metal panel overhead track door. An original, four-light fixed glass and wood window is located in the gable field. - **Noncontributing**





137 W. Lincoln Avenue - Contributing

This is a two- and one-half-story gable front Queen Anne-influenced Folk dwelling built ca. 1895. The dwelling has a roof of asphalt shingles, a continuous stone foundation, an exterior ivy-covered brick chimney and an exterior of weatherboard siding. On the main (N) façade is a partial-width, hipped roof porch with Tuscan wood columns on wood panel piers. The porch has an open wood railing in a geometrical pattern and a dentiled cornice. The main entrance retains its original, single-light and wood panel door with an original single-light transom. The main façade has chamfered bay with a decorative wood cut-out brackets and drop finial on the northeast corner. Above the second story windows on the main façade is a dentiled cornice. Also on this elevation is a tri-part attic window with a central arched window. In the gable field is a simple sunburst and vergeboard detail. Windows are original, one-over-one double hung wood sash and have simple wood cornice surrounds. The dwelling has been expanded off the rear façade with a two-story addition built ca. 1990.



To the rear of the dwelling is an original, frame garage/shed. It has a gambrel roof of asphalt shingles, a weatherboard exterior and a ca. 1985, large overhead track garage door with two false crossbeam patterns. In the upper portion of the façade is a vertical board false "bay door" with crossbeams.

- Contributing



138 W. Lincoln Avenue - Contributing

Located at 138 W. Lincoln Avenue is a two- and one-half-story gabled ell Queen Anne-style dwelling. The sign on the house says it was built ca. 1875 but the present appearance is more indicative of a ca. 1895 date. The house has a central hipped roof with projecting gable bays of asphalt shingles, a central interior brick chimney, a foundation of stone and the exterior has a narrow weatherboard siding. On the main (S) elevation is a partial-width, shed roof porch with milled wood posts and railing and a wood floor. The main entrance retains an original, single-light glass and wood door with a simple wood cornice and surround. Above the doors are rectangular panels in a swag design. Windows in the dwelling are original, one-over-one double hung wood sash design with simple wood cornice surrounds. A large picture window on the first floor of the main elevation has a multi-light transom. On the dwelling's east elevation is a bay window on the first floor level with the central window having a multi-light transom. Gable fields on the west and east elevations have decorative shingles and a single attic window. In the gable fields of the main façade are original decorative wood shingles and two, single-light fixed windows. A decorative milled vergeboard is at the gable eave. Milled brackets, similar to the vergeboard design, are on the porch. On the west elevation is an original, single-story, partial-width entry porch with a hipped roof supported by milled posts and railings with milled brackets.

To the rear of the dwelling is a ca. 1925 garage with a front gable asphalt shingle roof, a weatherboard exterior, an exterior end brick chimney and ca. 1990 overhead track metal panel garage door.

- Contributing





140 A & B W. Lincoln Avenue - Noncontributing

This is a ca. 1990, frame duplex.

There is a detached two bay garage located directly in front of duplex. **-Noncontributing**



141 W. Lincoln Avenue – Contributing (ARC Case 01-07)

This is a two-story, frame, gabled ell Folk dwelling built ca. 1900. The house has a gable roof of asphalt shingles, an interior brick chimney, a continuous stone foundation and an exterior of aluminum siding. The house has two entrances on the main (N) façade; one is located in the projecting gable bay, the other in the ell. Both entrances have original, six-light glass and wood panel doors with exterior wood panel screen doors. Above each door is a large steeply pitched wooden canopy. Each entrance leads to a set of curved poured concrete steps. The first floor windows on the main façade are original, eight-light casement design with simple wood cornice surrounds. Other windows are one-over-one double hung wood sash. In the projecting gable bays of the second story are paired one-over-one double hung wood sash windows with a wood cornice with decorative molding and wood surrounds. The rear elevation has an original, single-story shed roof rear wing and a small, ca. 1930, two-story addition that possibly contains bathrooms on either floor. On the rear façade of the ca. 1930 addition is an enclosed porch with screened, wood frame panels.

Located to the rear of the dwelling is a ca. 1915, single-bay, frame garage with an exterior of aluminum siding, a front gable roof of asphalt shingles and no visible door. Flanking the door opening are engaged milled wood posts.

- Contributing





200 W. Lincoln Avenue - Contributing

Located at 200 W. Lincoln Avenue is a two-story, frame, gable front Folk dwelling built ca. 1905. The house has a gable roof of asphalt shingles, an interior brick chimney, a stucco-covered concrete foundation and exterior of asbestos shingles. On the main (S) façade is a single-story shed roof porch with original Tuscan wood columns and a railing with milled wood balusters. The main entrance retains its original, six-panel wood door. Windows are original, two-over-two rectangular double hung wood sash. On the first floor of the main façade is a large fixed, single-light window with a stained glass transom. In the gable field is a rectangular attic single-light fixed attic window. At the gable eave is a king post and verge board. On the rear façade is an original, single-story, frame wing reconstructed ca.1970.

Located off the northeast corner of the dwelling is a ca. 1930, two-bay, frame garage with an exterior of shiplap siding, a gable roof and original twenty-wood panel overhead track garage doors. - **Contributing**





203 W. Lincoln Avenue - Contributing

This is a two-story rectangular American Foursquare style dwelling built ca. 1915. The house has a hipped roof of asphalt shingles, a rock-faced continuous concrete block foundation, an interior brick chimney and an exterior of synthetic siding. On the main (N) elevation is a single-story, full-width porch enclosed with screen panels and supported by rock-faced concrete block piers. The main entrance retains its original, oval-light glass and wood door with an exterior, nine-light glass and wood storm door. Adjacent to the entrance is a large, single-light fixed window with a multi-light transom. Both the window and entrance have simple wood cornice surrounds. On the second-story of the main façade is a tri-part bay window with two, one-over-one double hung wood sash windows flanking the central single-light fixed window with a single-light transom. At the roofline is a hipped roof dormer with two, single-light attic windows. On the east elevation are two-story, bay windows with a similar window pattern as the main facade. Windows throughout the dwelling are primarily original, one-over-one double hung wood sash with simple wood cornice surrounds. On the rear façade an original enclosed porch on first floor with living space above. The rear facade enclosed porch has original wood casement windows with multi-light transoms.



To the rear of the dwelling and facing Lill Avenue is an original, two-bay garage with a hipped roof of asphalt shingles, an exterior of vinyl siding, a continuous concrete block foundation and two, twenty-four wood panel overhead track garage doors. - **Contributing**



204 W. Lincoln Avenue - Contributing

Located at 204 W. Lincoln Avenue is a two-story, frame, gabled ell Folk dwelling built ca. 1880 and remodeled ca. 1980. The house has a concrete and stone foundation, a gable roof of asphalt shingles, an exterior wall brick chimney and an exterior weatherboard siding. On the main (S) façade is a ca. 1980, single-story shed roof entry bay with an original, four-light glass and wood panel door. Windows are ca. 1980, nine-over-nine, vinyl clad double hung sash on the first floor and original, six-over-six double hung wood sash on the second floor. All windows retain their original wood cornice surrounds. On the west façade is an original, two-story, gable roof wing with a hipped roof of asphalt shingles, an exterior of weatherboard siding and original glass and wood doors.

Located to the rear of the dwelling is a ca. 1925, single-story, two-bay, frame garage with an exterior of weatherboard, a hipped roof of asphalt shingles and two, original, four-light and twelve-wood panel overhead track doors. Located at the roofline on the main façade is a triangular wall dormer with a fixed, single-light window. - **Contributing**





209 W. Lincoln Avenue - Contributing

This is a two- and one-half-story rectangular American Foursquare dwelling built ca. 1910. The house has a hipped roof of asphalt shingles with a small wood baluster widow's walk at the peak, a weatherboard exterior, a central interior brick chimney and a continuous stone foundation. On the main façade is a single-story, full-width porch with Tuscan wood columns and a ca. 1990, wood baluster railing. The main entrance is centrally located on the main façade within a square projecting entry bay and retains its original, single-light glass and wood door with a single-light transom. Windows in the dwelling are original, one-over-one double hung wood sash with simple wood cornice surrounds on the first floor and wood surrounds on the second floor. The second story of the main façade has a central circular window set in a wood frame. At the roofline of the main (N) façade is a gable roof dormer with gable returns and paired, one-over-one double hung wood sash windows with multi-diamond light upper sashes.

To the rear of the dwelling is an original, frame, single-bay garage with a front gable roof of asphalt shingles, a vertical board exterior and a ca. 1945, sixteen-wood panel overhead track door. - **Contributing**



212 W. Lincoln Avenue - Contributing

Located at 212 W. Lincoln Avenue is a one- and one-half-story, frame, gabled ell Folk Victorian dwelling built ca. 1880. The house has a gable roof of wood shingles, a brick foundation and a weatherboard exterior. On the main (S) elevation is a partial-width shed roof porch set within the ell and supported by replacement milled wood posts and wood railing. The main entrance has an original, single-light glass and wood door. Windows are original, one-over-one double hung wood sash. Windows and doors have wood surrounds with corner blocks and saw tooth trim beneath a simple wood cornice. The first floor of the main façade has a large, projecting, hipped roof bay with a fixed, single-light window above which is a multi-light transom supported by large wood brackets. On the west elevation is a ca. 1955, frame, single-story addition with a side gable roof, an exterior brick chimney and sliding glass doors on its west facade. On the rear façade of the dwelling is an original wing. Attached to this original rear wing is another single-story addition of its western façade. Surrounding the house and property is a wood post and wood picket fence painted beige to match the house.



To the rear of the dwelling is an original, two-bay carriage house converted into a garage ca. 1980. The garage has a side gable roof of wood shingles, a weatherboard exterior and two, six-sectioned, two-light fixed glass and vertical board wood doors. At the roofline is a small gable roof wall dormer with a four-light, fixed window. Also on the property is an original, frame storage building reconstructed ca. 1970.

- Contributing



213 W. Lincoln Avenue - Contributing

Located at 213 W. Lincoln Avenue is a one-and-one-half-story side-gabled Craftsman dwelling built ca. 1925. The house has a side gable roof of asphalt shingles, a stucco exterior and an interior brick chimney. On the main (N) elevation is a full-width, inset porch with large square corner columns, a closed stucco railing and a ca. 1990, milled wood frieze. The main entrance has a ca. 1980, single-light glass and wood door with an aluminum and glass storm door. Adjacent to the main entrance on the east is a large single-light window with a single-light transom flanked by wood shutters. On the entrance's west is a single-light fixed window with a wood surround. On the main façade is a large gable roof dormer with a triple set of one-over-one double hung wood sash windows, the center window being slightly larger than the others. Windows in the dwelling are largely of replacement one-over-one double hung vinyl sash design.



Off the southwest corner of the dwelling is an original, single-bay garage with a hipped roof asphalt shingles, a stucco exterior and a ca. 1950, sixteen-wood panel overhead track garage door. - **Contributing**



217 W. Lincoln Avenue - Contributing

Located at 217 W. Lincoln Avenue is a one-and one-half-story, frame, gabled ell Folk dwelling built ca. 1890. The house has a gable roof of asphalt shingles, an exterior of stucco, a ca. 1940 exterior wall brick chimney and a stucco-covered continuous stone foundation. On the main (N) façade is a ca. 1920, partial-width, shed and hipped roof porch with Tuscan wood columns, wood stairs and a square wood baluster railing. The main entrance has a ca. 1980, glass and wood door. Windows are original, six-over-six double hung wood sash windows with simple wood cornice surrounds. On the south façade is an original, single-story gable roof wing with a ca. 1980 gable roof extension off the west façade with an entrance and an exterior of vinyl siding.

Located off the southwest corner of the dwelling is a ca. 1945, single-bay, frame garage with a front gable roof of asphalt shingles, an exterior of vinyl siding and an original, twelve-wood panel overhead track garage door. – **Noncontributing**





222 W. Lincoln Avenue - Contributing

Located at 222 W. Lincoln Avenue is a one- and one-half-story gabled-ell Folk dwelling with Craftsman influences, built ca. 1880. The house was enlarged ca. 1920 with an added rear two-story addition with a concrete and cobblestone chimney. The house has a stucco-covered brick foundation, a gable roof of asphalt shingles, an interior concrete and cobblestone chimney and an exterior of weatherboard siding. On the main (S) façade is an original hipped roof porch enclosed ca. 1920 to become a sun porch with weatherboard siding, wood steps, a Craftsman style, multi-light glass and wood door with multi-light glass and wood panel sidelights and one-over-one double hung wood sash windows. The interior main entrance retains its original, single-light glass and wood door. Windows are ca. 1990, one-over-one and six-over-six vinyl clad double hung sash with original wood cornice surrounds. On the first floor of the projecting bay is a ca. 1990, hipped roof bay window supported by wood brackets. Above the porch on the main façade is a set of four, short, four-light fixed windows and another single, four-light fixed window at the southwest corner.

Located to the rear of the dwelling is an original, two-story, frame, carriage house remodeled ca. 1930 into a garage. The building has a gable roof of asphalt shingles, an exterior of shiplap siding and a replacement overhead track garage door. – **Contributing**





223 W. Lincoln Avenue - Contributing

Located at this address is a two-story, frame, gable front Folk dwelling built ca. 1880. The house has a stucco-covered brick foundation, a gable roof of asphalt shingles, an interior brick chimney and exterior of vinyl siding. On the main (N) façade is a full-width, shed roof porch with original Tuscan wood columns and a square wood baluster railing resting on a foundation of rock-faced concrete block piers with ca. 1990, milled panels infill. The main entrance has a ca. 1990, glass and wood door. Windows are ca. 1990, one-over-one rectangular double hung vinyl sash. However, the windows flanking the main entrance are original, tow-over-two glass and wood fixed design.

At the rear is an original, one- and one-half-story, frame garage reconstructed ca. 1990 with an exterior of vinyl siding, a side gable roof of asphalt shingles and replacement vertical board hinged double doors.

– **Noncontributing**





228 W. Lincoln Avenue - Contributing

Located at 228 W. Lincoln Avenue is a two-and-one-half-story, frame side-gabled Colonial Revival dwelling built ca. 1930, with a roof of asphalt shingles, a poured concrete and brick foundation, an exterior end stone chimney and an exterior of aluminum siding. On the main (S) façade is the recessed main entrance with an original, six-light glass and wood panel door with a wood box panel frame. Flanking the entrance are fluted pilasters and above is an arched, wood pediment with a sunburst pattern. The first floor of the main façade has a large, original, twenty-light picture window flanked by four-over-four double hung wood sash windows above which is a scalloped wood cornice and slightly flared hipped roof hood beneath which is a canvas awning. Other windows in the dwelling are original, six-over-six double hung wood sash with canvas awnings. A secondary entrance on the west elevation has an original, six-light glass and wood door. On the northwest corner of the dwelling is a ca. 1940, small flat roof addition.

At the rear of the dwelling is an original, frame, two-bay garage with a steeply-pitched gable front roof, an exterior of clapboard siding and two, sixteen-wood panel overhead track garage doors. In the gable field are decorative shingles and a square, six-light fixed window. - **Contributing**





229 W. Lincoln Avenue – Contributing (ARC Case 05-06)

Located at 229 W. Lincoln Avenue is a one-and-one-half-story side-gabled Craftsman dwelling built ca. 1920. The house has a roof of asphalt shingles, an interior brick chimney and an original exterior of stucco. On the main (N) elevation is an original gable roof porch enclosed with four-over-one, vertical-light double hung wood sash windows. The main entrance has an original, four-light glass and wood door with original, narrow, two-light glass and wood sidelights and an original, four-light transom. Windows in the dwelling are original, three-over-one-vertical light double hung wood sash with wood surrounds. On the main façade roofline is a large shed roof dormer with a set of four, two-over-one double hung wood sash windows. On the east elevation is a projecting, hipped roof bay with four, narrow, single-light windows with two-light transoms. Adjacent to this bay is a row of three, three-vertical-light glass and wood windows. The dwelling and enclosed porch have exposed roof rafters and knee brace brackets at the eaves.

To the rear of the dwelling is an original, gable front, frame garage with a front gable roof of asphalt shingles, an exterior of wood shingles and two, triple-sectioned, four-light and four-rectangular-wood-panel sliding garage doors. In the gable field is a four-light fixed attic window with a wood surround.

- Contributing





234 W. Lincoln Avenue – Contributing (ARC Case 02-03)

Located at this address is a two-and-one-half-story cross-gabled dwelling built in the Dutch Colonial style ca. 1910. The house has a continuous ashlar-faced concrete block foundation, a gambrel and gable roof of asphalt shingles and an interior brick chimney. The first floor of this dwelling has an exterior of ashlar-faced concrete block while the second story has weatherboard siding. On the main (S) facade is an original, single-story, full-width porch enclosed ca. 1980 with weatherboard siding and six-over-six double hung wood sash windows. The recessed main entrance has a glass and wood panel door with a three-light transom. Windows in the main section of the dwelling are original, one-over-one rectangular double hung wood sash. In the gable fields are original wood shingles and the gable field on the main façade has a Palladian motif attic window. On the east façade is a ca. 1945, two-story gable addition and an original, hipped roof, single-story lateral porch with square wood columns and enclosed ca. 1945 with an exterior of weatherboard siding and an exterior wall brick chimney.

To the rear of the dwelling is an original, single-bay, frame garage with a clipped gable roof of asphalt shingles, an exterior of weatherboard siding and a ca. 1980, glass and metal garage door. Located above the door is a three-light fixed glass and wood window. – **Contributing**





235 W. Lincoln Avenue - Contributing

Located at 235 W. Lincoln Avenue is a two-story, brick and stucco rectangular Folk dwelling built ca. 1906. The house has a continuous brick foundation, a hipped roof of asphalt shingles, an interior brick chimney and exterior of stucco. On the main (N) façade is an original one-story, hipped roof porch with stucco covered brick piers and which was enclosed ca.1930 for a sunroom with original, four-over-one vertical-light double hung wood sash windows. The main entrance has a ca. 1930, six-light glass and wood door and three-light glass and wood panel sidelights. Windows are original, one-over-one rectangular double hung wood sash with original wood surrounds. At the roofline on the main and east façades are gable roof wall dormers with a single-light fixed attic window. Also on the east façade is a two-story, projecting bay with three, one-over-one double hung wood sash windows.

At the rear is a ca. 1970 frame garage. – **Noncontributing**

Photo request denied.



238 W. Lincoln Avenue - Contributing

Located at 238 W. Lincoln Avenue is a two-story gabled ell Folk Victorian dwelling built ca. 1880. The house has a gable roof of asphalt shingles, an interior brick chimney, a brick foundation and exterior of aluminum siding which replaced the ca. 1950 stucco finish. On the main (S) and east facades is a one-story wraparound porch with original milled columns, wood fan brackets, a spindled frieze and milled wood railing. The main entrance retains its original, oval-light, stained glass and wood-panel door. Windows are both original, double hung one-over-one wood sash and ca. 1990, one-over-one vinyl sash; all with wood surrounds. Also on the east façade is a one-story bay window with original, recessed wood panels, vergeboard wood brackets and three, one-over-one double hung wood sash windows. On the second story, the windows have original, pedimented wood cornices. On the east façade is a ca. 1990, one-story, lateral addition with an exterior of weatherboard siding, a side gable roof, one-over-one double hung vinyl sash windows, a continuous brick foundation and an exterior wall brick chimney.

Located to the rear of the dwelling is a ca. 1970, two-bay, frame garage with an exterior of aluminum siding, a side gable roof of asphalt shingles and two, sixteen-wood panel overhead track doors. – **Noncontributing**





239 W. Lincoln Avenue - Contributing

Located at 239 W. Lincoln Avenue is a two-story gable front Folk dwelling built ca. 1910. The house has an exterior of masonite siding, a continuous foundation of rock-faced concrete block, a flanged gable roof of asphalt shingles and an interior brick chimney. On the main (N) façade is a full-width, single-story porch enclosed ca. 1960 for a sunroom with four-over-four double hung wood sash windows, masonite shingle siding, a large picture window with a three-light transom and flanked by four-over-four double hung wood sash windows. The main entrance has a wood panel door with a simple wood cornice surround above which is a small projecting gable over a concrete stoop with ca. 1980 wrought iron railings. Windows are ca. 1960, one-over-one rectangular double hung wood sash with wood surrounds and flanking wood shutters on the main façade. A louvered triangular metal attic vent is in the apex of the gable field.



Of the northwest corner of the dwelling is a ca. 1960, single-bay, frame garage with a hipped roof of asphalt shingles, an exterior of masonite siding and a metal panel overhead track door. – **Noncontributing**



244 W. Lincoln Avenue - Contributing

This is a one- and one-half story side-gabled Queen Anne dwelling built ca. 1920. The house has a continuous brick foundation, a interior central concrete-covered chimney, an exterior or weatherboard siding and a slightly flared, side gable roof of asphalt shingles with a large, gambrel roof dormer with a paired set of windows on the main (S) façade. On the main (S) elevation is a small partial-width entry porch with bowed (?) Tuscan wood columns, wood panel end posts and a closed railing of weatherboard siding. The main entrance has an original, single-light glass and wood panel door set within a simple wood cornice surround. The first floor of the main façade has a large bay window supported by fanlight wood brackets. The east elevation has a secondary entrance with a single-light glass and wood door above which is an original, shed roof canopy supported by fanlight wood brackets. The west elevation has a bay window. Windows in dwelling are original, one-over-one double hung wood sash with wood surrounds. The eaves are oversized with exposed rafters. Gable fields have decorative wood shingle detailing, decorative wood trim and paired, one-over-one double hung wood sash windows. On the rear façade is a ca. 1955, one-story addition with an exterior of weatherboard and an entry on the east façade with a hipped roof wood canopy.

Located to the rear of the dwelling is a ca. 1965 frame garage. - **Noncontributing**



245 W. Lincoln Avenue - Contributing

Located at 245 W. Lincoln Avenue is a two-story rectangular Prairie and Colonial Revival-influenced American Foursquare. The dwelling has a hipped roof of asphalt shingle, a central interior brick chimney, a continuous rock-faced concrete block foundation and an exterior of wide weatherboard siding on the first floor and board and batten on the upper story which would have replaced its original stucco exterior. The main (N) façade entrance has a paneled wood door and a wood and screen exterior door. The entrance is set within a wood frame with fluted pilasters and an arched cornice with dentils. Flanking the entrance are paired, six-light casement windows with a three-light transom with flanking wood plank windows and wood cornice surrounds. Windows throughout the dwelling are primarily six-over-six double hung wood sash. On the west elevation is a small, one-story hipped roof addition with one-over-one double hung wood sash windows. The dwelling has expanded at the rear with a two-story addition and the second story's west elevation has a large triangular stained glass window. On the east elevation of the main (original) section, is a two-story, bay window with six-over-six double hung wood sash windows.

To the rear of the dwelling is a ca. 1970, single-bay, frame garage with hipped roof of asphalt shingles, a weatherboard exterior and a ca. 1990, metal panel overhead track door. - **Noncontributing**





247 W. Lincoln Avenue - Noncontributing

This site has a ca. 1985, two-story frame side-gabled Colonial Revival style dwelling.



248 W. Lincoln Avenue – Contributing (ARC Case 01-21)

Located at 248 W. Lincoln Avenue is a one- and- one-half-story side-gabled Craftsman dwelling built ca. 1920. The house has a side gable roof of asphalt shingles, a stucco-covered continuous concrete foundation and exterior of masonite shingle siding. On the main (S) façade is a full-width, shed roof porch with original stucco-covered brick columns and a solid stucco-covered concrete railing. The main entrance retains its original, multi-light glass and wood door. Windows are ca. 1995, one-over-one double hung rectangular wood sash. On the main façade is a large gable roof dormer with paired, one-over-one double hung Craftsman-style windows. At the eaves are knee brace brackets. On the west façade is a one-story gable roof wing with knee brace brackets. A hardiplank shingle exterior has been installed the gable fields.

Located to the rear of the dwelling is a ca. 1960 frame garage. – **Noncontributing**